

ADA 086180

DDC FILE COPY

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE

LEVEL II

READ INSTRUCTIONS
BEFORE COMPLETING FORM

1. REPORT NUMBER	2. GOVERNMENT AGENCY	3. RECIPIENT'S CATALOG NUMBER
AD-A086180		8
4. TITLE (and Subtitle) Phase I Inspection Report Lake Adirondack Dam Upper Hudson River Basin, Hamilton County, NY Inventory No. NY 621		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) George Koch, P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, New York 12233		8. CONTRACT OR GRANT NUMBER(s) DACW-51-79-C-0001
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Con- servation/ 50 Wolf Road Albany, New York 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza/ New York District, CofE New York, New York 10007		12. REPORT DATE 21 May 1980
		13. NUMBER OF PAGES
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited. THIS DOCUMENT IS BEST QUALITY PRACTICABLE. THE COPY FURNISHED TO DDC CONTAINED A SIGNIFICANT NUMBER OF PAGES WHICH DO NOT REPRODUCE LEGIBLY.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from above)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Lake Adirondack Dam Hamilton County Indian Lake		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which need to be evaluated and remedied.		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

Additional hydrologic investigations are required to more accurately determine the site specific characteristics of the watershed. Using the Corps of Engineer's Screening Criteria for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped by the outflows resulting from all storms exceeding 42% of the Probable Maximum Flood (PMF). A flood wave analysis, assuming a breaching of the dam, indicates that water surface levels downstream of the dam could reach depths which would pose significant danger to residents. The spillway is, therefore, adjudged as seriously inadequate and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam.

Structural stability analyses based on available information, indicate that factors of safety against both overturning and sliding are less than desirable. When the dam is subjected to severe loading conditions (1/2 PMF, PMF, ice load) the safety factors fall to critical levels. Further investigation of the stability is needed including subsurface investigations and concrete coring. These studies should determine the condition of the dam and its foundation and develop accurate cross sections of the dam. This information should then be incorporated into a detailed stability evaluation. Appropriate modifications to the dam should then be made as required.

It is recommended that within 3 months of the date of final approval of this report, a hydrologic investigation of the structure should be undertaken. Investigation of the structural stability of the dam should be commenced within 6 months. Within 18 months of the final approval of this report, appropriate remedial measures for both the spillway inadequacy and the stability problems

should be completed. In the interim, a detailed emergency operation plan and warning system should be developed and implemented.

There were several additional deficiencies which should also be corrected. The surface of the concrete on the dam, especially on the spillway section, was spalled and deteriorated. There were several cracks in the concrete sections, and there were leaks through the joints between sections of the spillway. A wet area was noted beyond the toe of the downstream slope on the eastern end of the dam. There were trees growing on the downstream slope of the embankment. These deficiencies should be corrected within 12 months of the date of final approval of this report.

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UPPER HUDSON RIVER BASIN

LAKE ADIRONDACK DAM


HAMILTON COUNTY, NEW YORK

INVENTORY NO. N.Y. 621

(6) PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

Lake Adirondack Dam (Inventory Number NY 621),
Upper Hudson River Basin, ~~Adirondack Park~~
Hamilton County, New York. Phase I Inspection
Reports

(10) George / Koch



(11) 21 May 80

(12) S.S.

(15) DACW 51-79-2-0001

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED

CONTRACT NO. DACW-51-79-C0001

NEW YORK DISTRICT CORPS OF ENGINEERS

JANUARY, 1980

393970

80 7 3

058

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Accession For	
NTIS Grant	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Date _____	
Accession Codes	
Dist	Area and/or special
A 23	GP

20 7 3 058

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE ADIRONDACK DAM
I.D NO. N.Y. 621
#169-929
UPPER HUDSON RIVER BASIN
HAMILTON COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOTECHNICAL DATA	4
2.2 DESIGN RECORDS	4
2.3 CONSTRUCTION RECORDS	4
2.4 OPERATION RECORD	4
2.5 EVALUATION OF DATA	4
3 VISUAL INSPECTION	5
3.1 FINDINGS	5
3.2 EVALUATION OF OBSERVATIONS	6
4 OPERATION AND MAINTENANCE PROCEDURES	7
4.1 PROCEDURE	7
4.2 MAINTENANCE OF DAM	7
4.3 WARNING SYSTEM IN EFFECT	7
4.4 EVALUATION	7

	<u>PAGE NO.</u>
5 HYDROLOGIC/HYDRAULIC	8
5.1 DRAINAGE AREA CHARACTERISTICS	8
5.2 ANALYSIS CRITERIA	8
5.3 SPILLWAY CAPACITY	8
5.4 RESERVOIR CAPACITY	8
5.5 FLOODS OF RECORD	8
5.6 OVERTOPPING POTENTIAL	8
5.7 EVALUATION	8
6 STRUCTURAL STABILITY	9
6.1 EVALUATION OF STRUCTURAL STABILITY	9
7 ASSESSMENT/RECOMMENDATIONS	11
7.1 ASSESSMENT	11
7.2 RECOMMENDED MEASURES	12

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC ENGINEERING DATA AND COMPUTATIONS
- D. STRUCTURAL STABILITY ANALYSES
- E. REFERENCES
- F. DRAWINGS

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Lake Adirondack Dam (I.D. N.Y. 621)
State Located: New York
County: Hamilton
Watershed: Upper Hudson River Basin
Stream: Carroll Brook
Date of Inspection: October 18, 1979

ASSESSMENT

Examination of available documents and a visual inspection of the dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which need to be evaluated and remedied.

Additional hydrologic investigations are required to more accurately determine the site specific characteristics of the watershed. Using the Corps of Engineer's Screening Criteria for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped by the outflows resulting from all storms exceeding 42% of the Probable Maximum Flood (PMF). A flood wave analysis, assuming a breaching of the dam, indicates that water surface levels downstream of the dam could reach depths which would pose significant danger to residents. The spillway is, therefore, adjudged as seriously inadequate and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a seriously inadequate spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam.

Structural stability analyses based on available information, indicate that factors of safety against both overturning and sliding are less than desirable. When the dam is subjected to severe loading conditions (1/2 PMF, PMF, ice load) the safety factors fall to critical levels. Further investigation of the stability is needed including subsurface investigations and concrete coring. These studies should determine the condition of the dam and its foundation and develop accurate cross sections of the dam. This information should then be incorporated into a detailed stability evaluation. Appropriate modifications to the dam should then be made as required.

It is recommended that within 3 months of the date of final approval of this report, a hydrologic investigation of the structure should be undertaken. Investigation of the structural stability of the dam should be commenced within 5 months. Within 18 months of the final approval of this report, appropriate remedial measures for both the spillway inadequacy and the stability problems

should be completed. In the interim, a detailed emergency operation plan and warning system should be developed and implemented.

There were several additional deficiencies which should also be corrected. The surface of the concrete on the dam, especially on the spillway section, was spalled and deteriorated. There were several cracks in the concrete sections, and there were leaks through the joints between sections of the spillway. A wet area was noted beyond the toe of the downstream slope on the eastern end of the dam. There were trees growing on the downstream slope of the embankment. These deficiencies should be corrected within 12 months of the date of final approval of this report.

George Koch

George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No. 45937

Approved By:

Clark H. Benn

Col. Clark H. Benn
New York District Engineer

Date:

21 MAY 1980

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
LAKE ADIRONDACK DAM
I.D. No. NY 621
#169-928
UPPER HUDSON RIVER BASIN
HAMILTON COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam

The Lake Adirondack Dam is composed of a concrete wall with earth fill both upstream and downstream of the wall. The spillway section, located near the center of the dam, is a masonry structure which has been covered with concrete.

The dam is 750 feet long and has a maximum height of 17.5 feet. The concrete wall extends about 3 feet above the earth fill and has a top width of 1.5 feet. The upstream slope of the earth fill is 1 vertical on 2 horizontal. The downstream slope is a 1 vertical on 2 1/2 horizontal.

The spillway is 99 feet long and consists of four adjacent sections. Three of the sections a total of 79 feet in length have crest elevations which are approximately one foot below the top of the dam. The crest of the remaining section, which is 20 feet long, is about one foot below the crest of the other sections. The crest of this lowest section is formed by a 3 1/2 inch timber fastened to the concrete.

A reservoir drain consisting of a 24 inch diameter gate valve and a 42 inch by 50 inch rectangular outlet conduit is located to the west of the spillway. The control for this gate valve is on the top of the dam.

b. Location

The dam is located in the Town of Indian Lake on N.Y. State Route 28. It is approximately one half mile east of the village of Indian Lake.

c. Size Classification

The dam is 17.5 feet high and the maximum storage capacity has been estimated to be 1182 acre-feet. Therefore, the dam is in the intermediate size category as defined by the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification

The dam is classified as "high" hazard due to the presence of a major state highway, four homes and the town's sewage disposal plant downstream of the dam.

e. Ownership

The dam is owned by the town of Indian Lake. The Town Supervisor is Richard Perdue. His phone number is (518) 648-5256.

f. Purpose of Dam

The dam is used to maintain the water surface of Adirondack Lake for recreational purposes.

g. Design and Construction History

No information was available about the original design of the dam. A portion of the dam was constructed in 1910. The height of the dam was increased in 1931. Plans for these modifications, prepared by C.S. Carroll were available and have been included in Appendix F.

h. Normal Operating Procedures

Water flows over an ungated spillway. There are no regular operating procedures. This year the drain was opened and the lake level lowered for the winter in an attempt to kill weeds in the lake.

1.3

PERTINENT DATA

<u>a. Drainage Area (acres)</u>	883
<u>b. Discharge at Dam (cfs)</u>	
Spillway Water Surface at elevation 1658.2	60
Spillway Water Surface at elevation 1659.0	338
Reservoir Drain-Water Surface at elevation 1659.0	94
<u>c. Elevation (USGS Datum)</u>	
Top of Dam	1659.0
First Step on Spillway (3 Sections)	1658.2
Lower Step on Spillway (1 Middle Section)	1657.25
Invert of Reservoir Drain	1645.0
<u>d. Reservoir-Surface Area</u>	(acres)
Top of Dam	186.6
Spillway Crest (Elevation 1657.25)	166.4
<u>e. Storage Capacity</u>	(acre-feet)
Top of Dam	1182
Spillway Crest (Elevation 1657.25)	874

f. Dam

Type: Concrete Wall with earth fill upstream and downstream.
Dam Length(ft.) 750
Crest Elevation 1659.0
Crest Width (Concrete Wall)(ft.) 1.5
Embankment Slopes (V:H) Upstream 1 on 2
Downstream 1 on 2 1/2

g. Spillway

Type: Ungated, four section concrete overflow with one 20 foot wide portion whose crest is 1 foot lower than the other 3 sections.
Length-Total (feet) 99

h. Reservoir Drain

Type: 24 inch diameter gate valve flowing into a 42 inch by 50 inch cast-in-place outlet conduit.
Control: Ludlow gate valve on top of dam.

SECTION 2: ENGINEERING DATA

2.1 GEOTECHNICAL DATA

a. Geology

The Lake Adirondack Dam is located in the Adirondack Highlands physiographic province of New York State. The original rock was sedimentary with large intrusions of igneous rocks (anorthosites, granites, gabbros). Much of this rock has been metamorphosed by heat, pressure, folding and faulting. Surface features of the rock reflects the effects of glaciation. A review of the "Brittle Structures Map of the State of New York" indicated that there are no faults in the immediate vicinity of the dam.

The surficial soils are the result of glaciations during the Cenozoic Era, the last of which was the Wisconsin glaciation.

b. Subsurface Investigations

The only subsurface information available was a general subsurface profile contained on the 1931 reconstruction plans. This profile indicated that the western end of the dam is founded on gravel while the rest of the structure is supported on ledge rock.

2.2 DESIGN RECORDS

No design records for the original construction of this dam were available. Plans prepared by C.S. Carroll for the modifications made in 1931 were available and have been included in Appendix F.

2.3 CONSTRUCTION RECORDS

No construction records were available.

2.4 OPERATION RECORDS

No operation records were available.

2.5 EVALUATION OF DATA

The data presented in this report was obtained from the Department of Environmental Conservation files. While the information was somewhat limited, it appears to be reliable and adequate for Phase I inspection purposes.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of the Lake Adirondack Dam was conducted on October 18, 1979. The weather was overcast and the temperature was in the fifties. The water surface at the time of the inspection was 1.7 feet below the spillway crest. The valve on the reservoir drain was partially opened on the date of the inspection.

b. Dam

The main dam generally appeared to be in satisfactory condition. There were, however, several deficiencies noted on the structure.

Surface deterioration of the concrete and cracks in the central wall at the western end of the dam were noted. The remaining sections of the wall which were exposed appeared to be in satisfactory condition. There were no indications of sloughing, subsidence, or movement of the fill on either the upstream or downstream slope. Some minor bank erosion had occurred on the upstream face at the western end of the dam. There were a number of trees growing on the downstream slope.

There was a wet area beyond the toe of the embankment section on the eastern end of the dam. This area extended for approximately 100 feet along the toe. Standing water was observed in the area, but no points of concentrated seepage were located. It was unclear whether the wet area was caused by seepage through the dam's foundation or springs from the hillside beyond the dam.

c. Spillway

Several deficiencies were noted on the spillway section of the dam. There was minor spalling and deterioration across the spillway. In some areas, the deterioration was more severe. The facing material was peeling off in sections on one of the channel walls beyond the base of the spillway. There were also several cracks in the concrete forming the spillway and downstream walls. One crack on the western wall downstream of the spillway extends across the entire width of the wall.

There were several leaks through the spillway section. The primary leaks were at the joints between the different sections of the spillway. Water was emerging on the downstream face at about mid-height of the spillway. The apron at the downstream toe of the western end of the spillway was very wet due to the seepage. Drain pipes have been installed in the wall at the downstream edge of this apron. Water was flowing from several of these pipes.

d. Reservoir Drain

Visual observations of the reservoir drain did not reveal any serious deficiencies. The gate valve control on the top of the dam appeared to be in good condition and operable. The condition of the cast-in place outlet conduit was satisfactory. There was one construction joint in the conduit which was not perfectly aligned. Concrete had been used to fill the separation.

e. Downstream Channel

Bedrock was exposed in the channel beyond the downstream toe of the spillway section. Concrete has been poured on the rock immediately downstream, to fill some surface irregularities. This concrete was deteriorated and had been removed in some spots. Beyond this area, outflows pass through a 72 inch corrugated metal pipe under Route 28. The condition of the channel in this section and beyond was generally satisfactory.

3.2 Evaluation of Observations

Visual inspection revealed several deficiencies on this structure. The following items were noted:

1. Surface deterioration of the concrete and cracks in the central wall at the western end of the dam.
2. A wet area beyond the toe of the embankment at the eastern end of the dam.
3. Deterioration of concrete on the spillway.
4. Leaks through construction joints on the spillway.
5. Trees growing on the downstream slope of the earth fill.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURE

4.1 PROCEDURES

There are no regular operation procedures for this dam. This year, the valve on the reservoir drain was partially opened in September. This action was taken in an attempt to kill some of the weeds in the lake.

4.2 MAINTENANCE OF DAM

Routine maintenance on the dam is performed by the Town of Indian Lake.

4.3 WARNING SYSTEM IN EFFECT

No apparent warning system is present.

4.4 EVALUATION

The operation and maintenance procedures for this dam appear to be generally satisfactory. Increased maintenance efforts are required to correct the deficiencies which exist.

SECTION 5: HYDROLOGIC/HYDRAULIC

5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the watershed draining into the reservoir pool area was made using the USGS 15 minute quadrangles for Blue Mountain and Newcomb, New York. The drainage area is 883 acres and consists of wooded lands and the village of Indian Lake. Relief in the drainage area is moderate to steep with slopes ranging from 2 per cent in the western portion of the drainage area to 12 percent to the north of the reservoir.

5.2 ANALYSIS CRITERIA

The analysis of the floodwater retarding capability of this dam was performed using the Corps of Engineers HEC-1 computer program, Dam Safety version. This program uses the Clark Unit hydrograph method and the "Modified Puls" flood routing procedure. The spillway design flood selected for analysis was the PMF in accordance with the recommended guidelines for the U.S. Army Corps of Engineers.

5.3 SPILLWAY CAPACITY

The dam has an ungated spillway which is composed of four adjacent sections. The total length of the spillway is 99 feet. The spillway operates under weir flow conditions and was analyzed as a trapezoidal weir having a discharge coefficient which varied according to head. Coefficients used ranged from 3.09 to 3.51. The computed spillway capacity when the water surface is at the top-of-dam is 338 cfs.

5.4 RESERVOIR CAPACITY

Normal storage capacity of the reservoir between the spillway crest (elevation 1657.25) and the top of the dam (elevation 1659.0) is 20.2 acre feet which is equivalent to a runoff depth of 0.27 inches over the drainage area. Total storage capacity of the dam is estimated to be 1182 acre-feet.

5.5 FLOODS OF RECORD

No information was available regarding the occurrence of the maximum known flood.

5.6 OVERTOPPING POTENTIAL

Analysis using the Probable Maximum Flood (PMF) and one-half the PMF indicates that the dam does not have sufficient spillway capacity. For a PMF peak outflow of 1970 cfs, the dam would be overtopped to a computed depth of 0.77 feet. For the peak outflow from one-half the PMF, (Q=564 cfs), the depth of overtopping would be 0.19 feet. The dam would be overtopped by all storms exceeding 42% of the PMF inflow. Overtopping might result in the earth fill downstream of the concrete wall being eroded and creating an unstable condition.

5.7 Evaluation

Using the Corps of Engineers screening criteria for initial review of spillway adequacy, it has been determined that the dam would be overtopped by all storms exceeding 42% of the PMF inflow. A flood wave analysis, assuming a breaching of the dam, indicates that the water surface levels downstream of the dam could reach depths which pose a significant danger to residents.

The spillway is, therefore, adjudged to be seriously inadequate and the dam is assessed as unsafe, non-emergency.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

Visual inspection of the dam revealed some deterioration and cracking on the spillway section. In addition, cracks were noted in the top of the concrete wall which extends for the length of the dam. There was a wet area beyond the downstream toe on the eastern end of the dam.

b. Data Review and Stability Evaluation

Information used to perform the stability analysis was obtained from the 1931 reconstruction plans. However, some of the dimensions shown on the plans did not agree with actual measurements made at the time of inspection. The most serious discrepancies were on the spillway section. Dimensions used for the analysis were estimated based on all available data. More accurate information will be required in the future to perform additional stability analyses.

Stability analyses which were done studied two sections of the dam. Analyses were performed for the concrete wall with earth fill which comprises most of the dam, and for one portion of the spillway section. The section which was analyzed may not be the most critical section. However, there was not enough information available to analyze each portion of the spillway. The following conditions were analyzed for each case:

- a. Normal conditions with the reservoir level at spillway crest (elevation 1657.25);
- b. Reservoir level at spillway crest with an ice load of 10,000 lb.;
- c. One-half PMF, water flowing over the top of dam to a depth of 0.23 feet;
- d. PMF, water flowing over the top of dam to a depth of 0.83 feet;

The analyses performed (See Appendix D) indicate that the factors of safety against overturning and sliding for each of the sections are as follows:

<u>Concrete Wall Section</u>		<u>Factors of Safety</u>	
<u>Case</u>		<u>Overturning</u>	<u>Sliding</u>
a.	Reservoir level at ele. 1657.25	1.57	2.13
b.	Same as (a) plus an ice load of 10,000 lb/ft	.64	1.11
c.	One-half PMF, water flowing .23 feet over top of dam	.77	.42
d.	PMF, water flowing .83 feet over top of dam	.73	.40

<u>Spillway Section</u>		<u>Factors of Safety</u>	
<u>Case</u>		<u>Overturning</u>	<u>Sliding</u>
a.	Reservoir level at elevation 1657.25	1.24	1.40
b.	Same as (a) plus an ice load of 10,000 lb/ft	.37	.62
c.	One-half PMF, water flowing .23 feet over top of dam	1.00	1.12
d.	PMF, water flowing .83 feet over top of dam	.94	1.05

The stability analyses indicate that the stability of each section is deficient. The safety factors of the concrete wall section fall to unacceptable levels under flood flow conditions since the overtopping of the dam might result in the earth fill downstream of the wall being eroded. This removal would reduce the passive force acting on the wall. The safety factors of both sections are unacceptable when subjected to ice loading.

Further investigations and studies are required to better assess the stability of the structure. A series of subsurface explorations, including several through the earth fill downstream of the wall, and concrete cores should be taken to provide additional data concerning the dam. Information concerning the condition of the reinforcement within the dam should also be obtained. Field surveys should then be made and accurate cross sections of the dam should be developed. Stability analyses should then be performed using this data. Based on the results of these analyses, required modifications to the structure should be designed and implemented.

d. Seismic Stability

This dam is located in Seismic Zone 2. Due to the location, a seismic stability analysis was performed in accordance with Corps of Engineers guidelines. The seismic analysis was performed for normal conditions with the water level at the spillway crest (elevation 1657.25). For the concrete wall section, the safety factor against overturning with seismic considerations included is 1.47 and against sliding is 1.92. For the spillway section analyzed, the safety factor against overturning is 1.15 and against sliding is 1.24.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 Assessment

a. Safety

The Phase I inspection of the Lake Adirondack Dam revealed that the spillway is seriously inadequate and outflows from the one-half PMF event might overtop the dam. This overtopping would result in the earth fill downstream of the concrete wall being eroded and create an unstable condition. This instability could cause breaching of the dam and the resulting floodwave would significantly increase the hazard to downstream residents. For this reason, the dam has been assessed as unsafe, non-emergency.

In addition to the spillway inadequacy, analyses indicate that the stability of the structure is questionable. The factors of safety fall to critical levels under extreme loading conditions (one-half PMF, PMF, ice loading). Other deficiencies noted on this structure, such as deterioration of concrete, leaks in the spillway section, and a wet area beyond the downstream toe on the eastern end of the dam could present a hazard unless appropriate repairs are made.

b. Adequacy of Information

The information which was available for the preparation of this report was somewhat limited. Plans for the modifications to the dam made in 1931 were used, but some of the dimensions shown on the plans did not agree with measurements made at the time of the inspection. No information concerning the reservoir capacity was available. Since some information was not available, certain assumptions had to be made to perform the analyses for this report.

c. Need for Additional Investigations

Since the spillway has been assessed as seriously inadequate, additional detailed hydrologic and hydraulic investigations are required to more accurately determine the site specific characteristics of the watershed.

Further investigation of the structural stability of the dam is also required. Each portion of the spillway section should be analyzed as well as the concrete wall with earth fill which comprises most of the dam. These studies should include subsurface and structural investigations to obtain information about the condition of the structure and its foundation. Accurate cross sections of the dam should be developed. This information should then be incorporated into a detailed stability evaluation.

The wet area beyond the toe of the embankment on the eastern end of the dam should be investigated. Attempts should be made to determine the source of the water which ponds in this area and a method to either eliminate the seepage or treat the area should be advised.

d. Urgency

The additional hydrologic and hydraulic investigations which are needed should be commenced within 3 months of the date of final approval of this report. Investigations of the structural stability of the dam should be commenced within 6 months.

Mitigating measures deemed necessary as a result of the investigation and repairs required should be completed within 18 months of the date of final approval of this report.

7.2 RECOMMENDED MEASURES

- a. After the hydrological investigation has been completed, mitigating measures dealing with the seriously inadequate spillway capacity should be determined.
- b. After the structural stability analysis has been completed, appropriate remedial work should be undertaken.
- c. The surface deterioration and cracks in the concrete on both the main dam and spillway sections should be repaired.
- d. Leaks through the joints on the spillway should be repaired.
- e. Based on the findings concerning the wet area, required treatments should be undertaken.
- f. Trees growing on the downstream slope of the earth fill should be cut.

APPENDIX A

PHOTOGRAPHS



Western End of Dam - Erosion Has Exposed a Portion of Concrete Wall




Concrete Wall on Eastern End of Dam - Note Trees on Downstream Slope



Wet Area Beyond Toe at Eastern End of Dam



Standing Water in Wet Area on Eastern End of Dam



Spillway Section of Dam.



Reservoir Drain - Control on Top of Dam; Outlet Near Center of Picture



Spillway Looking in Easterly Direction - Note Four Sections on Spillway



Seepage Through Joint Between Two of the Sections of Spillway



Western End of Spillway - Note Cracks on Wingwalls and Spillway Section



Flowing Drain Pipe - Located in Wall Below Apron Shown in Picture Above



Loose Facing Material on Spillway Wingwall



Area on Wingwall Where Facing Material Has Been Removed

APPENDIX B

VISUAL INSPECTION CHECKLIST

1

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam ADIRONDACK LAKE DAM
Fed. I.D. # 621 DEC Dam No. 169-928
River Basin UPPER HUDSON
Location: Town INDIAN LAKE County HAMILTON
Stream Name CARROLL BROOK
Tributary of INDIAN RIVER
Latitude (N) 43° 46.8' Longitude (W) 74° 15.4'
Type of Dam CONCRETE WALL WITH EARTH FILL UPSTREAM & DOWNSTREAM
Hazard Category C
Date(s) of Inspection 10/18/79
Weather Conditions OVERCAST - 50°
Reservoir Level at Time of Inspection 1.7' ± BELOW SPILLWAY CREST

b. Inspection Personnel R. WARRENDER, W. LYNICK

c. Persons Contacted (Including Address & Phone No.) _____

d. History:

Date Constructed 1910 Date(s) Reconstructed 1936

Designer _____

Constructed By _____ PWA

Owner _____

2) Embankment

a. Characteristics

- (1) Embankment Material GRANULAR FILL ON EITHER SIDE OF WALL.
- (2) Cutoff Type CONCRETE WALL - SOME SURFACE DETERIORATION & CRACKS THROUGH WALL ESP. ON WESTERN END
- (3) Impervious Core - CONCRETE CUTOFF WALL
- (4) Internal Drainage System NONE
- (5) Miscellaneous _____

b. Crest

- (1) Vertical Alignment SATISFACTORY
- (2) Horizontal Alignment SATISFACTORY
- (3) Surface Cracks ~~NOT~~ APPARENT NONE APPARENT
- (4) Miscellaneous _____

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1 ON 3
- (2) Undesirable Growth or Debris, Animal Burrows NONE
- (3) Sloughing, Subsidence or Depressions SOME EROSION & SLOUGHING ON WESTERN END NEAR BEACH

(4) Slope Protection RIPRAP ONLY ON WESTERN END

(5) Surface Cracks or Movement at Toe NONE

d. Downstream Slope

(1) Slope (Estimate - V:H) 1:1 ON WESTERN END 1:2 ON EASTERN END

(2) Undesirable Growth or Debris, Animal Burrows TREES ON DOWNSTREAM SLOPE ON EITHER END.

(3) Sloughing, Subsidence or Depressions NONE

(4) Surface Cracks or Movement at Toe NONE

(5) Seepage SOME ON SPILLWAY SEE SEC. 9.
WET AREA BEYOND TOE AT EASTERN END - POSSIBLY
SEEPAGE

(6) External Drainage System (Ditches, Trenches; Blanket) NONE

(7) Condition Around Outlet Structure SATISFACTORY

(8) Seepage Beyond Toe WET AREA AT EASTERN END - COULD
BE SEEPAGE OR MIGHT BE HILLSIDE SPRINGS

e. Abutments - Embankment Contact

(1) Erosion at Contact NONE

(2) Seepage Along Contact NO

3) Drainage System

a. Description of System SEVERAL DRAINAGE PIPES IN CONCRETE SPILLWAY SECTION

b. Condition of System SATISFACTORY

c. Discharge from Drainage System SLIGHT DISCHARGE FROM SEVERAL OF THE PIPES,

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) NONE

5) Reservoir

- a. Slopes FLAT
- b. Sedimentation NONE APPARENT
- c. Unusual Conditions Which Affect Dam NONE

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) RTE. 28
4 HOMES SEWAGE PLANT
- b. Seepage, Unusual Growth NONE
- c. Evidence of Movement Beyond Toe of Dam NONE
- d. Condition of Downstream Channel RTE 28 - 72" CSP

7) Spillway(s) (Including Discharge Conveyance Channel)

- GRAVITY & BUTTRESS - CONCRETE UNGATED CREST - 4 SECTIONS
- a. General MINOR CONCRETE SPALLING & DETERIORATION - MAINLY AT JOINTS
- b. Condition of Service Spillway DETERIORATION AT CONCRETE JOINTS
SURFACE DETERIORATION SPALLED CONCRETE SURFACE
COVERINGS - SEEPAGE THROUGH SOME JOINTS

c. Condition of Auxiliary Spillway _____

d. Condition of Discharge Conveyance Channel NATURAL BEDROCK WITH
CONCRETE AREAS OVER ROCK IRREGULARITIES - CONCRETE
PATCHES REMOVED IN SPOTS - ROCK RUBBLE - SATISFACTORY
WALLS ON WEST SIDE OF CHANNEL - GOOD CONDITION

8) Reservoir Drain/Outlet

Type: Pipe _____ Conduit X Other _____

Material: Concrete X Metal _____ Other _____

Size: 42" WIDE X 50" HIGH Length 20' ± INCLINED sect. up to valve

Invert Elevations: Entrance 1645.0 Exit _____

Physical Condition (Describe): _____ Unobservable _____

Material: CONCRETE - CAST-IN-PLACE

Joints: OKAY Alignment SLIGHT MISALIGN CR COULD BE
EXCESS CONC. PROJECTING AT JOINT

Structural Integrity: SATISFACTORY

Hydraulic Capability: SATISFACTORY - NO BLOCKAGE


Means of Control: Gate _____ ^{24"}Valve X Uncontrolled _____

Operation: Operable X Inoperable _____ Other _____

Present Condition (Describe): SATISFACTORY

9) Structural

- a. Concrete Surfaces MINOR SPALLING & DETERIORATION - WATER FLOW DETERIORATES ON PLUNGE APRON BELOW ~~APR~~ LOW SPILL SECTION WEST APRON FASCIA - 2' X 3' AREA WHERE CONCRETE FACING IS BROKEN FROM THE WALL ITSELF.
- b. Structural Cracking ON DOWNSTREAM ABUTMENT WALL AT WEST END OF SPILLWAY THRU ENTIRE WALL THICKNESS & DOWN INTO WALL 6' ±
- c. Movement - Horizontal & Vertical Alignment (Settlement) NONE APPARENT
- d. Junctions with Abutments or Embankments. JOINTS - CRACK AT WEST END OF SPILLWAY IN WING WALL
- e. Drains - Foundation, Joint, Face MIDDLE OF SPILLWAY - PIPE COMING OUT - NO DISCHARGE BUT WET INSIDE PIPES ON WALL NEAR WESTERN END ON APRON - BOTH DISCHARGING.
- f. Water Passages, Conduits, Sluices ^{RES.} DRAIN CONDUIT - SIDEWALL JOINT DISPLACEMENT (<1")
- g. Seepage or Leakage (SEE DIAGRAM BELOW) 1/2 LENGTH OF ABUTMENT WALL AT A HAS SEEPAGE COMING THROUGH. APRON BELOW SECTION AB HAD PIPE DRAINS & SURFACE SEEPAGE - THIS SECTION HAD THE MOST SEEPAGE OBSERVED. BOTH JOINTS B & C HAD SOME SEEPAGE. JOINT AT D HAD APPROXIMATELY 1 gpm FLOW EXITING AT POINT ABOUT 6' ABOVE THE APRON.



- h. Joints - Construction, etc. CONCRETE DETERIORATION AT
SEVERAL JOINTS
- i. Foundation BEDROCK
- j. Abutments
- k. Control Gates GATE & MECHANISM ON DRAIN APPEARS GOOD
- l. Approach & Outlet Channels SATISFACTORY
- m. Energy Dissipators (Plunge Pool, etc.) NATURAL BEDROCK - SATISFACTORY
- n. Intake Structures
- o. Stability
- p. Miscellaneous

APPENDIX C
HYDROLOGIC/HYDRAULIC
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>1659.0</u>	<u>186.6</u>	<u>1182</u>
2) Design High Water (Max. Design Pool)	<u> </u>	<u> </u>	<u> </u>
3) Auxiliary Spillway Crest (1st STEP)	<u>1658.2</u>	<u> </u>	<u> </u>
4) Pool Level with Flashboards	<u> </u>	<u> </u>	<u> </u>
5) Service Spillway Crest (2nd STEP) (Top of 3 1/2' TIMBER)	<u>1657.25</u>	<u>166.4</u>	<u>874</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u> </u>
2) Spillway @ Maximum High Water - W.S. AT 1659.0	<u>338</u>
3) Spillway @ Design High Water	<u> </u>
4) Spillway @ Auxiliary Spillway Crest Elevation (1st STEP) W.S. AT 1658.2	<u>59.9</u>
5) Low Level Outlet - W.S. AT 1657	<u>94.3</u>
6) Total (of all facilities) @ Maximum High Water	<u>432.3</u>
7) Maximum Known Flood	<u> </u>

CREST:

ELEVATION: 1659.0Type: CONCRETE WALLWidth: 1.25 ft.Length: 750 ftSpillover FOUR SECTION SPILLWAYLocation NEAR CENTER OF DAM

SPILLWAY:

1ST STEP
~~PRINCIPAL~~2ND STEP
~~EMERGENCY~~

<u>1658.2</u>	Elevation	<u>1657.25</u>
<u>OVERFLOW</u>	Type	<u>OVERFLOW</u>
<u>79.1'</u>	Width	<u>20.1'</u>

Type of Control

<u>✓</u>	Uncontrolled	<u>✓</u>
----------	--------------	----------

Controlled:

	Type	
	(Flashboards; gate)	

	Number	
--	--------	--

	Size/Length	
--	-------------	--

	Invert Material	
--	-----------------	--

	Anticipated Length of operating service	
--	--	--

	Chute Length	
--	--------------	--

	Height Between Spillway Crest & Approach Channel Invert (Weir Flow)	
--	---	--

OUTLET STRUCTURES/EMERGENCY DRAWDOWN FACILITIES:

Type: Gate ✓ Sluice _____ Conduit ✓ Penstock _____Shape: CIRCULAR GATE - RECTANGULAR CONDUITSize: 24" 42" WIDE X 50" HIGHElevations: Entrance Invert 1645.0Exit Invert 1635.2 - ESTIMATED

Tailrace Channel: Elevation _____

HYDROMETEROLOGICAL GAGES:

Type: NONE

Location: _____

Records: _____

Date - _____

Max. Reading - _____

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

24" DIAMETER GATE

DRAINAGE AREA: 1.38 SQ MI - 883.2 ACRES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: MOSTLY WOODS - PART SWAMP & VILLAGE

Terrain - Relief: MODERATE TO STEEP

Surface - Soil: GRAVEL & GLACIAL TILL

Runoff Potential (existing or planned extensive alterations to existing
(surface or subsurface cond'tions)

NORMAL POTENTIAL

Potential Sedimentation problem areas (natural or man-made; present or future)

NONE

Potential Backwater problem areas for levels at maximum storage capacity
including surcharge storage:

NONE

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the
Reservoir perimeter:

Location: NONE

Elevation: .. -

Reservoir:

Length @ Maximum Pool _____ (Miles)

Length of Shoreline (@ Spillway Crest) _____ (Miles)

PROJECT GRID

JOB	LAKE ADIRONDACK DAM	SHEET NO.	2	CHECKED BY		DATE	
SUBJECT	HYDROLOGY COMPUTATIONS			COMPUTED BY	RLW	DATE	1/2/80
CLARK UNIT HYDROGRAPH:							
$L = 1.86 \text{ mi.}$		$S_{0.5} = 14.336$		$109\% \text{ at } 982'$		$E_{10} = 1660$	
				$85\% \text{ at } 8348'$		$E_{85} = 16810$	
		$S = 0.5$					
$R = \frac{(1.76)(1.86)^{.339}(.5)^{.258}}{(14.336)^{.82}} = 1.8$							
$T_c \rightarrow \text{FROM OTHER COMPUTATIONS} = 2.3$							
PRECIPITATION:							
TP-40 - 6 hr - 1050 mi $\rightarrow 20.5 \text{ in}$							
HR-33 - 24 hr - 20050 mi $\rightarrow 17.5 \text{ in} \rightarrow 6 \text{ hr Fraction is } 130\%$							
USE TP40 RNIN FOR 6 hr AS 100% AND ADJUST THE OTHER PERCENTAGES ACCORDINGLY							
12 hr 107.7%							
24 hr 113%							
48 hr 125%							
$TRSPC = 1 - \frac{.2048}{(1.38)^{1.7718}} = .716$							
LOSS DATA: 1.0" CONTINUOUS = .1"							
BASE FLOW = 2 cfs/sq mi $2(1.38) = 2.76$							

PROJECT GRID

JOB	LAKE ADIRONDACK DAM	SHEET NO.	1	CHECKED BY		DATE	
SUBJECT	HYDROLOGY COMPUTATIONS			COMPUTED BY	RLW	DATE	1/2/80

ELEVATIONS OF DAM

TOP OF DAM	1659.0
FIRST STEP ON SPILLWAY	1658.2
LOWER STEP ON SPILLWAY	1657.25

DRAINAGE AREA - PLANNIMETERED FROM 15 MINUTE QUADS

FROM BLUE MOUNTAIN QUAD	- 1.31 sq. mi.
FROM NEWCOMB QUAD	- .07 sq. mi.
	<u>1.38 sq. mi. = 883.2 ACRES</u>

SURFACE AREA - PLANNIMETERED FROM 15 MINUTE QUAD

LAKE ON QUAD (STATED ELEVATION 1680)	- 156.4 ACRES
1680 CONTOUR	- 396.8 ACRES

RELATIVE DISTANCE BETWEEN NORMAL LAKE LEVEL AND TOP OF DAM = $1659.0 - 1657.25 = 1.75'$

$$\frac{(396.8 - 156.4) \text{ ACRES}}{X \text{ ACRES}} = \frac{20.5}{1.7547}$$

$X = 20.16 \text{ ACRES}$

ASSUME SURFACE AREA AT ELEVATION 1657.25 = 156.4 ACRES

SURFACE AREA AT ELEVATION 1659.0 = 186.6 ACRES

SURFACE AREA AT 1659.0 - 17.5 = 164.15 = 0 ACRES

PROJECT GRID

JOB LAKE ADIRONDACK DAM		SHEET NO. 3	CHECKED BY	DATE
SUBJECT HYDRAULIC COMPUTATIONS		COMPUTED BY RLW		DATE 12/28/79

SPILLWAY CAPACITY COMPUTATIONS

1659.0' < 31' * 24' * 223' * 258' >

1658.2' 1657.25'

FOR 'C' VALUES IN WEIR FORMULA USE TABLE E-9 KING & BRATER
FOR TRAPEZOIDAL SECTION WITH VERTICAL UPSTREAM FACE

WATER SURFACE AT ELEVATION 1658.2

$$Q = CLH^{3/2} = (3.22)(20.1)(.95)^{3/2} = 59.93 \text{ cfs}$$

WATER SURFACE AT ELEVATION 1659.0

$$Q = (3.51)(20.1)(1.75)^{3/2} + (3.09)(79)(.8)^{3/2} = 163.3 + 174.7 = 338.0 \text{ cfs}$$

RESERVOIR DRAIN CAPACITY - WATER SURFACE AT TOP OF DAM

$$Q = A\sqrt{2gH} = 3.14\sqrt{2(32.2)(14)} = 94.3 \text{ cfs}$$

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 (AM SAFETY VERSION JULY 1978)
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APR 79

1 A1 LAKE ANIRUNDACK DAM
 2 A PHF WITH RATIOS - ANALYSIS
 3 A3 DATE
 4 B 200
 5 B1 5

6 J 1 3 1
 7 J1 .42 .5 1.0
 8 K 0 1
 9 K1

INFLUX HYDROGRAPH

10 M 1 0 1.38
 11 P 0 17.5 111 123 132 142
 12 T
 13 V 2.3 1.8
 14 X 2.8 2.8 1
 15 K 1 1

K1 PLUTED HYDROGRAPH AT DAM NO BREACH

17 Y
 18 Y1 1
 19 Y4657.25 658.2 659
 20 Y5 0 60 338
 21 SA 0 166.4 186.6
 22 SE 541.5 657.25 659.0
 23 \$657.25
 24 \$D 659 3.0 1.5 672
 25 K 1 1000
 26 K1 LOCATION TOE OF DAM
 27 Y
 28 Y1 1
 29 Y6 .05 .05 639 662 20 .99
 30 Y7 0 662 125 650 240 642 265 639
 31 Y7 265 642 450 650 580 660

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274

275

276

277

278

279

280

281

282

283

284

285

286

287

288

289

290

291

292

293

294

295

296

297

298

299

300

301

302

303

304

305

306

307

308

309

310

311

312

313

314

315

316

317

318

319

320

321

322

323

324

325

326

327

328

329

330

331

332

333

334

335

336

337

338

339

340

341

342

343

344

345

346

347

348

349

350

351

352

353

354

355

356

357

358

359

 FLUID HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79
 MODIFIED FOR HONEYWELL APR 79

RUN DATE 03/20/80

LAKE ADIRONDACK DAM
 PHE WITH RATIOS - ANALYSIS
 DATE

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

JOB SPECIFICATION
 N7 MHR 0 NMN 15 IDAY 0 IMIN 0 METRC 0 NSTAN 0
 200 0 JOPER 5 NWT 0 LROPT 0 TRACE 0

MULTI-PLAN ANALYSES TO BE PERFORMED
 RATIOS= 0.42 0.50 1.00
 NPLAN= 1 NRATIO= 3 LRATIO= 1

***** SUB-AREA RUNOFF COMPUTATION *****

INFLW HYDROGRAPH
 ISTAQ 1 ICOMP 0 ISTAQ 1 INAME 1 ISTAGE 0 IAUQ 0
 JPLT 0 JPLT 0 JPLT 0 JPLT 0 JPLT 0 JPLT 0

HYDROGRAPH DATA
 INVCG 1 IUNG 0 TAREA 1.38 SNAP 0.0 TRSDA 1.38 TRSFC 0.72 RATIC 0.0 ISNOW 0 ISAME 1 LOCAL 0
 SPFE 0.0 PMS 17.50 R6 111.00 R12 123.00 R24 132.00 R48 142.00 R72 0.0 R96 0.0

PRECIP DATA
 LOSS DATA
 LROPT 0 STRKR 0.0 RTIOL 1.00 ERAIN 0.0 STRKS 0.0 RTICK 1.00 CNSTL 0.10 ALSHX 0.0 RTIMP 0.0
 TC= 2.30 R= 1.8C NTAM= 0

UNIT HYDROGRAPH DATA
 STRTQ= 2.80 QRCNS= 2.80 RTICK= 1.00
 UNIT HYDROGRAPH 44 END-OF-PERIOD ORDINATES, LAG= 2.03 PCLRS, CP= C.64 VOL= 1.00
 12. 43. 87. 136. 188. 234. 266. 283. 284. 262.
 229. 199. 174. 151. 131. 114. 99. 87. 75. 55.
 57. 30. 43. 38. 33. 28. 25. 22. 19. 16.
 14. 11. 9. 8. 7. 6. 5. 4. 3. 2.
 3. 2. 1. 0. 0. 0. 0. 0. 0. 0.

END-OF-PERIOD FLOW
 MD.0A 0 HR.00 PERIOD 1 LOSS 0.00 EXCS 0.00 RAIN 0.00
 1.01 0.15 1.01 0.30 1.01 0.45 1.01 0.60 1.01 0.75 1.01 0.90 1.01 1.00 1.01 1.15 1.01 1.30 1.01 1.45 1.01 1.60 1.01 1.75 1.01 1.90 1.01 2.00 1.01 2.15 1.01 2.30 1.01 2.45 1.01 2.60 1.01 2.75 1.01 2.90 1.01 3.00 1.01 3.15 1.01 3.30 1.01 3.45 1.01 3.60 1.01 3.75 1.01 3.90 1.01 4.00 1.01 4.15 1.01 4.30 1.01 4.45 1.01 4.60 1.01 4.75 1.01 4.90 1.01 5.00 1.01 5.15 1.01 5.30 1.01 5.45 1.01 5.60 1.01 5.75 1.01 5.90 1.01 6.00 1.01 6.15 1.01 6.30 1.01 6.45 1.01 6.60 1.01 6.75 1.01 6.90 1.01 7.00 1.01 7.15 1.01 7.30 1.01 7.45 1.01 7.60 1.01 7.75 1.01 7.90 1.01 8.00 1.01 8.15 1.01 8.30 1.01 8.45 1.01 8.60 1.01 8.75 1.01 8.90 1.01 9.00 1.01 9.15 1.01 9.30 1.01 9.45 1.01 9.60 1.01 9.75 1.01 9.90 1.01 10.00 1.01 10.15 1.01 10.30 1.01 10.45 1.01 10.60 1.01 10.75 1.01 10.90 1.01 11.00 1.01 11.15 1.01 11.30 1.01 11.45 1.01 11.60 1.01 11.75 1.01 11.90 1.01 12.00 1.01 12.15 1.01 12.30 1.01 12.45 1.01 12.60 1.01 12.75 1.01 12.90 1.01 13.00 1.01 13.15 1.01 13.30 1.01 13.45 1.01 13.60 1.01 13.75 1.01 13.90 1.01 14.00 1.01 14.15 1.01 14.30 1.01 14.45 1.01 14.60 1.01 14.75 1.01 14.90 1.01 15.00 1.01 15.15 1.01 15.30 1.01 15.45 1.01 15.60 1.01 15.75 1.01 15.90 1.01 16.00 1.01 16.15 1.01 16.30 1.01 16.45 1.01 16.60 1.01 16.75 1.01 16.90 1.01 17.00 1.01 17.15 1.01 17.30 1.01 17.45 1.01 17.60 1.01 17.75 1.01 17.90 1.01 18.00 1.01 18.15 1.01 18.30 1.01 18.45 1.01 18.60 1.01 18.75 1.01 18.90 1.01 19.00 1.01 19.15 1.01 19.30 1.01 19.45 1.01 19.60 1.01 19.75 1.01 19.90 1.01 20.00 1.01 20.15 1.01 20.30 1.01 20.45 1.01 20.60 1.01 20.75 1.01 20.90 1.01 21.00 1.01 21.15 1.01 21.30 1.01 21.45 1.01 21.60 1.01 21.75 1.01 21.90 1.01 22.00 1.01 22.15 1.01 22.30 1.01 22.45 1.01 22.60 1.01 22.75 1.01 22.90 1.01 23.00 1.01 23.15 1.01 23.30 1.01 23.45 1.01 23.60 1.01 23.75 1.01 23.90 1.01 24.00 1.01 24.15 1.01 24.30 1.01 24.45 1.01 24.60 1.01 24.75 1.01 24.90 1.01 25.00 1.01 25.15 1.01 25.30 1.01 25.45 1.01 25.60 1.01 25.75 1.01 25.90 1.01 26.00 1.01 26.15 1.01 26.30 1.01 26.45 1.01 26.60 1.01 26.75 1.01 26.90 1.01 27.00 1.01 27.15 1.01 27.30 1.01 27.45 1.01 27.60 1.01 27.75 1.01 27.90 1.01 28.00 1.01 28.15 1.01 28.30 1.01 28.45 1.01 28.60 1.01 28.75 1.01 28.90 1.01 29.00 1.01 29.15 1.01 29.30 1.01 29.45 1.01 29.60 1.01 29.75 1.01 29.90 1.01 30.00 1.01 30.15 1.01 30.30 1.01 30.45 1.01 30.60 1.01 30.75 1.01 30.90 1.01 31.00 1.01 31.15 1.01 31.30 1.01 31.45 1.01 31.60 1.01 31.75 1.01 31.90 1.01 32.00 1.01 32.15 1.01 32.30 1.01 32.45 1.01 32.60 1.01 32.75 1.01 32.90 1.01 33.00 1.01 33.15 1.01 33.30 1.01 33.45 1.01 33.60 1.01 33.75 1.01 33.90 1.01 34.00 1.01 34.15 1.01 34.30 1.01 34.45 1.01 34.60 1.01 34.75 1.01 34.90 1.01 35.00 1.01 35.15 1.01 35.30 1.01 35.45 1.01 35.60 1.01 35.75 1.01 35.90 1.01 36.00 1.01 36.15 1.01 36.30 1.01 36.45 1.01 36.60 1.01 36.75 1.01 36.90 1.01 37.00 1.01 37.15 1.01 37.30 1.01 37.45 1.01 37.60 1.01 37.75 1.01 37.90 1.01 38.00 1.01 38.15 1.01 38.30 1.01 38.45 1.01 38.60 1.01 38.75 1.01 38.90 1.01 39.00 1.01 39.15 1.01 39.30 1.01 39.45 1.01 39.60 1.01 39.75 1.01 39.90 1.01 40.00 1.01 40.15 1.01 40.30 1.01 40.45 1.01 40.60 1.01 40.75 1.01 40.90 1.01 41.00 1.01 41.15 1.01 41.30 1.01 41.45 1.01 41.60 1.01 41.75 1.01 41.90 1.01 42.00 1.01 42.15 1.01 42.30 1.01 42.45 1.01 42.60 1.01 42.75 1.01 42.90 1.01 43.00 1.01 43.15 1.01 43.30 1.01 43.45 1.01 43.60 1.01 43.75 1.01 43.90 1.01 44.00 1.01 44.15 1.01 44.30 1.01 44.45 1.01 44.60 1.01 44.75 1.01 44.90 1.01 45.00 1.01 45.15 1.01 45.30 1.01 45.45 1.01 45.60 1.01 45.75 1.01 45.90 1.01 46.00 1.01 46.15 1.01 46.30 1.01 46.45 1.01 46.60 1.01 46.75 1.01 46.90 1.01 47.00 1.01 47.15 1.01 47.30 1.01 47.45 1.01 47.60 1.01 47.75 1.01 47.90 1.01 48.00 1.01 48.15 1.01 48.30 1.01 48.45 1.01 48.60 1.01 48.75 1.01 48.90 1.01 49.00 1.01 49.15 1.01 49.30 1.01 49.45 1.01 49.60 1.01 49.75 1.01 49.90 1.01 50.00 1.01 50.15 1.01 50.30 1.01 50.45 1.01 50.60 1.01 50.75 1.01 50.90 1.01 51.00 1.01 51.15 1.01 51.30 1.01 51.45 1.01 51.60 1.01 51.75 1.01 51.90 1.01 52.00 1.01 52.15 1.01 52.30 1.01 52.45 1.01 52.60 1.01 52.75 1.01 52.90 1.01 53.00 1.01 53.15 1.01 53.30 1.01 53.45 1.01 53.60 1.01 53.75 1.01 53.90 1.01 54.00 1.01 54.15 1.01 54.30 1.01 54.45 1.01 54.60 1.01 54.75 1.01 54.90 1.01 55.00 1.01 55.15 1.01 55.30 1.01 55.45 1.01 55.60 1.01 55.75 1.01 55.90 1.01 56.00 1.01 56.15 1.01 56.30 1.01 56.45 1.01 56.60 1.01 56.75 1.01 56.90 1.01 57.00 1.01 57.15 1.01 57.30 1.01 57.45 1.01 57.60 1.01 57.75 1.01 57.90 1.01 58.00 1.01 58.15 1.01 58.30 1.01 58.45 1.01 58.60 1.01 58.75 1.01 58.90 1.01 59.00 1.01 59.15 1.01 59.30 1.01 59.45 1.01 59.60 1.01 59.75 1.01 59.90 1.01 60.00 1.01 60.15 1.01 60.30 1.01 60.45 1.01 60.60 1.01 60.75 1.01 60.90 1.01 61.00 1.01 61.15 1.01 61.30 1.01 61.45 1.01 61.60 1.01 61.75 1.01 61.90 1.01 62.00 1.01 62.15 1.01 62.30 1.01 62.45 1.01 62.60 1.01 62.75 1.01 62.90 1.01 63.00 1.01 63.15 1.01 63.30 1.01 63.45 1.01 63.60 1.01 63.75 1.01 63.90 1.01 64.00 1.01 64.15 1.01 64.30 1.01 64.45 1.01 64.60 1.01 64.75 1.01 64.90 1.01 65.00 1.01 65.15 1.01 65.30 1.01 65.45 1.01 65.60 1.01 65.75 1.01 65.90 1.01 66.00 1.01 66.15 1.01 66.30 1.01 66.45 1.01 66.60 1.01 66.75 1.01 66.90 1.01 67.00 1.01 67.15 1.01 67.30 1.01 67.45 1.01 67.60 1.01 67.75 1.01 67.90 1.01 68.00 1.01 68.15 1.01 68.30 1.01 68.45 1.01 68.60 1.01 68.75 1.01 68.90 1.01 69.00 1.01 69.15 1.01 69.30 1.01 69.45 1.01 69.60 1.01 69.75 1.01 69.90 1.01 70.00 1.01 70.15 1.01 70.30 1.01 70.45 1.01 70.60 1.01 70.75 1.01 70.90 1.01 71.00 1.01 71.15 1.01 71.30 1.01 71.45 1.01 71.60 1.01 71.75 1.01 71.90 1.01 72.00 1.01 72.15 1.01 72.30 1.01 72.45 1.01 72.60 1.01 72.75 1.01 72.90 1.01 73.00 1.01 73.15 1.01 73.30 1.01 73.45 1.01 73.60 1.01 73.75 1.01 73.90 1.01 74.00 1.01 74.15 1.01 74.30 1.01 74.45 1.01 74.60 1.01 74.75 1.01 74.90 1.01 75.00 1.01 75.15 1.01 75.30 1.01 75.45 1.01 75.60 1.01 75.75 1.01 75.90 1.01 76.00 1.01 76.15 1.01 76.30 1.01 76.45 1.01 76.60 1.01 76.75 1.01 76.90 1.01 77.00 1.01 77.15 1.01 77.30 1.01 77.45 1.01 77.60 1.01 77.75 1.01 77.90 1.01 78.00 1.01 78.15 1.01 78.30 1.01 78.45 1.01 78.60 1.01 78.75 1.01 78.90 1.01 79.00 1.01 79.15 1.01 79.30 1.01 79.45 1.01 79.60 1.01 79.75 1.01 79.90 1.01 80.00 1.01 80.15 1.01 80.30 1.01 80.45 1.01 80.60 1.01 80.75 1.01 80.90 1.01 81.00 1.01 81.15 1.01 81.30 1.01 81.45 1.01 81.60 1.01 81.75 1.01 81.90 1.01 82.00 1.01 82.15 1.01 82.30 1.01 82.45 1.01 82.60 1.01 82.75 1.01 82.90 1.01 83.00 1.01 83.15 1.01 83.30 1.01 83.45 1.01 83.60 1.01 83.75 1.01 83.90 1.01 84.00 1.01 84.15 1.01 84.30 1.01 84.45 1.01 84.60 1.01 84.75 1.01 84.90 1.01 85.00 1.01 85.15 1.01 85.30 1.01 85.45 1.01 85.60 1.01 85.75 1.01 85.90 1.01 86.00 1.01 86.15 1.01 86.30 1.01 86.45 1.01 86.60 1.01 86.75 1.01 86.90 1.01 87.00 1.01 87.15 1.01 87.30 1.01 87.45 1.01 87.60 1.01 87.75 1.01 87.90 1.01 88.00 1.01 88.15 1.01 88.30 1.01 88.45 1.01 88.60 1.01 88.75 1.01 88.90 1.01 89.00 1.01 89.15 1.01 89.30 1.01 89.45 1.01 89.60 1.01 89.75 1.01 89.90 1.01 90.00 1.01 90.15 1.01 90.30 1.01 90.45 1.01 90.60 1.01 90.75 1.01 90.90 1.01 91.00 1.01 91.15 1.01 91.30 1.01 91.45 1.01 91.60 1.01 91.75 1.01 91.90 1.01 92.00 1.01 92.15 1.01 92.30 1.01 92.45 1.01 92.60 1.01 92.75 1.01 92.90 1.01 93.00 1.01 93.15 1.01 93.30 1.01 93.45 1.01 93.60 1.01 93.75 1.01 93.90 1.01 94.00 1.01 94.15 1.01 94.30 1.01 94.45 1.01 94.60 1.01 94.75 1.01 94.90 1.01 95.00 1.01 95.15 1.01 95.30 1.01 95.45 1.01 95.60 1.01 95.75 1.01 95.90 1.01 96.00 1.01 96.15 1.01 96.30 1.01 96.45 1.01 96.60 1.01 96.75 1.01 96.90 1.01 97.00 1.01 97.15 1.01 97.30 1.01 97.45 1.01 97.60 1.01 97.75 1.01 97.90 1.01 98.00 1.01 98.15 1.01 98.30 1.01 98.45 1.01 98.60 1.01 98.75 1.01 98.90 1.01 99.00 1.01 99.15 1.01 99.30 1.01 99.45 1.01 99.60 1.01 99.75 1.01 99.90 1.01 100.00 1.01 100.15 1.01 100.30 1.01 100.45 1.01 100.60 1.01 100.75 1.01 100.90 1.01 101.00 1.01 101.15 1.01 101.30 1.01 101.45 1.01 101.60 1.01 101.75 1.01 101.90 1.01 102.00 1.01 102.15 1.01 102.30 1.01 102.45 1.01 102.60 1.01 102.75 1.01 102.90 1.01 103.00 1.01 103.15 1.01 103.30 1.01 103.45 1.01 103.60 1.01 103.75 1.01 103.90 1.01 104.00 1.01 104.15 1.01 104.30 1.01 104.45 1.01 104.60 1.01 104.75 1.01 104.90 1.01 105.00 1.01 105.15 1.01 105.30 1.01 105.45 1.01 105.60 1.01 105.75 1.01 105.90 1.01 106.00 1.01 106.15 1.01 106.30 1.01 106.45 1.01 106.60 1.01 106.75 1.01 106.90 1.01 107.00 1.01 107.15 1.01 107.30 1.01 107.45 1.01 107.60 1.01 107.75 1.01 107.90 1.01 108.00 1.01 108.15 1.01 108.30 1.01 108.45 1.01 108.60 1.01 108.75 1.01 108.90 1.01 109.00 1.01 109.15 1.01 109.30 1.01 109.45 1.01 109.60 1.01 109.75 1.01 109.90 1.01 110.00 1.01 110.15 1.01 110.30 1.01 110.45 1.01 110.60 1.01 110.75 1.01 110.90 1.01 111.00 1.01 111.15 1.01 111.30 1.01 111.45 1.01 111.60 1.01 111.75 1.01 111.90 1.01 112.00 1.01 112.15 1.01 112.30 1.01 112.45 1.01 112.60 1.01 112.75 1.01 112.90 1.01 113.00 1.01 113.15 1.01 113.30 1.01 113.45 1.01 113.60 1.01 113.75 1.01 113.90 1.01 114.00 1.01 114.15 1.01 114.30 1.01 114.45 1.01 114.60 1.01 114.75 1.01 114.90 1.01 115.00 1.01 115.15 1.01 115.30 1.01 115.45 1.01 115.60 1.01 115.75 1.01 115.90 1.01 116.00 1.01 116.15 1.01 116.30 1.01 116.45 1.01 116.60 1.01 116.75 1.01 116.90 1.01 117.00 1.01 117.15 1.01 117.30 1.01 117.45 1.01 117.60 1.01 117.75 1.01 117.90 1.01 118.00 1.01 118.15 1.01 118.30 1.01 118.45 1.01 118.60 1.01 118.75 1.01 118.90 1.01 119.00 1.01 119.15 1.01 119.30 1.01 119.45 1.01 119.60 1.01 119.75 1.01 119.90 1.01 120.00 1.01 120.15 1.01 120.30 1.01 120.45 1.01 120.60 1.01 120.75 1.01 120.90 1.01 121.00 1.01 121.15 1.01 121.30 1.01 121.45 1.01 121.60 1.01 121.75 1.01 121.90 1.01 122.00 1.01 122.15 1.01 122.30 1.01 122.45 1.01 122.60 1.01 122.75 1.01 122.90 1.01 123.00 1.01 123.15 1.01 123.30 1.01 123.45 1.01 123.60 1.01 123.75 1.01 123.90 1.01 124.00 1.01 124.15 1.01 124.30 1.01 124.45 1.01 124.60 1.01 124.75 1.01 124.90 1.01 125.00 1.01 125.15 1.01 125.30 1.01 125.45 1.01 125.60 1.01 125.75 1.01 125.90 1.01 126.00 1.01 126.15 1.01 126.30 1.01 126.45 1.01 126.60 1.01 126.75 1.01 126.90 1.01 127.00 1.01 127.15 1.01 127.30 1.01 127.45 1.01 127.60 1.01 127.75 1.01 127.90 1.01 128.00 1.01 128.15 1.01 128.30 1.01 128.45 1.01 128.60 1.01 128.75 1.01 128.90 1.01 129.00 1.01 129.15 1.01 129.30 1.01 129.45 1.01 129.60 1.01 129.75 1.01 129.90 1.01 130.00 1.01 130.15 1.01 130.30 1.01 130.45 1.01 130.60 1.01 130.75 1.01 130.90 1.01 131.00 1.01 131.15 1.01 131.30 1.01 131.45 1.01 131.60 1.01 131.75 1.01 131.90 1.01 132.00 1.01 132.15 1.01 132.30 1.01 132.45 1.01 132.60 1.01 132.75 1.01 132.90 1.01 133.00 1.01 133.15 1.01 133.30 1.01 133.45 1.01 133.60 1.01 133.75 1.01 133.90 1.01 134.00 1.01 134.15 1.01 134.30 1.01 134.45 1.01 134.60 1.01 134.75 1.01 134.90 1.01 135.00 1.01 135.15 1.01 135.30 1.01 135.45 1.01 135.60 1.01 135.75 1.01 135.90 1.01 136.00 1.01 136.15 1.01 136.30 1.01 136.45 1.01 136.60 1.01 136.75 1.01 136.90 1.01 137.00 1.01 137.15 1.01 137.30 1.01 137.45 1.01 137.60 1.01 137.75 1.01 137.90 1.01 138.00 1.01 138.15 1.01 138.30 1.01 138.45 1.01 138.60 1.01 138.75 1.01 138.90 1.01 139.00 1.01 139.15 1.01 139.30 1.01 139.45 1.01 139.60 1.01 139.75 1.01 139.90 1.01 140.00 1.01 140.15 1.01 140.30 1.01 140.45 1.01 140.

[illegible]

• 445
• 444
• 443
• 442
• 441
• 440
• 439
• 438
• 437
• 436
• 435
• 434
• 433
• 432
• 431
• 430
• 429
• 428
• 427
• 426
• 425
• 424
• 423
• 422
• 421
• 420
• 419
• 418
• 417
• 416
• 415
• 414
• 413
• 412
• 411
• 410
• 409
• 408
• 407
• 406
• 405
• 404
• 403
• 402
• 401
• 400
• 399
• 398
• 397
• 396
• 395
• 394
• 393
• 392
• 391
• 390
• 389
• 388
• 387
• 386
• 385
• 384
• 383
• 382
• 381
• 380
• 379
• 378
• 377
• 376
• 375
• 374
• 373
• 372
• 371
• 370
• 369
• 368
• 367
• 366
• 365
• 364
• 363
• 362
• 361
• 360
• 359
• 358
• 357
• 356
• 355
• 354
• 353
• 352
• 351
• 350
• 349
• 348
• 347
• 346
• 345
• 344
• 343
• 342
• 341
• 340
• 339
• 338
• 337
• 336
• 335
• 334
• 333
• 332
• 331
• 330
• 329
• 328
• 327
• 326
• 325
• 324
• 323
• 322
• 321
• 320
• 319
• 318
• 317
• 316
• 315
• 314
• 313
• 312
• 311
• 310
• 309
• 308
• 307
• 306
• 305
• 304
• 303
• 302
• 301
• 300
• 299
• 298
• 297
• 296
• 295
• 294
• 293
• 292
• 291
• 290
• 289
• 288
• 287
• 286
• 285
• 284
• 283
• 282
• 281
• 280
• 279
• 278
• 277
• 276
• 275
• 274
• 273
• 272
• 271
• 270
• 269
• 268
• 267
• 266
• 265
• 264
• 263
• 262
• 261
• 260
• 259
• 258
• 257
• 256
• 255
• 254
• 253
• 252
• 251
• 250
• 249
• 248
• 247
• 246
• 245
• 244
• 243
• 242
• 241
• 240
• 239
• 238
• 237
• 236
• 235
• 234
• 233
• 232
• 231
• 230
• 229
• 228
• 227
• 226
• 225
• 224
• 223
• 222
• 221
• 220
• 219
• 218
• 217
• 216
• 215
• 214
• 213
• 212
• 211
• 210
• 209
• 208
• 207
• 206
• 205
• 204
• 203
• 202
• 201
• 200
• 199
• 198
• 197
• 196
• 195
• 194
• 193
• 192
• 191
• 190
• 189
• 188
• 187
• 186
• 185
• 184
• 183
• 182
• 181
• 180
• 179
• 178
• 177
• 176
• 175
• 174
• 173
• 172
• 171
• 170
• 169
• 168
• 167
• 166
• 165
• 164
• 163
• 162
• 161
• 160
• 159
• 158
• 157
• 156
• 155
• 154
• 153
• 152
• 151
• 150
• 149
• 148
• 147
• 146
• 145
• 144
• 143
• 142
• 141
• 140
• 139
• 138
• 137
• 136
• 135
• 134
• 133
• 132
• 131
• 130
• 129
• 128
• 127
• 126
• 125
• 124
• 123
• 122
• 121
• 120
• 119
• 118
• 117
• 116
• 115
• 114
• 113
• 112
• 111
• 110
• 109
• 108
• 107
• 106
• 105
• 104
• 103
• 102
• 101
• 100
• 99
• 98
• 97
• 96
• 95
• 94
• 93
• 92
• 91
• 90
• 89
• 88
• 87
• 86
• 85
• 84
• 83
• 82
• 81
• 80
• 79
• 78
• 77
• 76
• 75
• 74
• 73
• 72
• 71
• 70
• 69
• 68
• 67
• 66
• 65
• 64
• 63
• 62
• 61
• 60
• 59
• 58
• 57
• 56
• 55
• 54
• 53
• 52
• 51
• 50
• 49
• 48
• 47
• 46
• 45
• 44
• 43
• 42
• 41
• 40
• 39
• 38
• 37
• 36
• 35
• 34
• 33
• 32
• 31
• 30
• 29
• 28
• 27
• 26
• 25
• 24
• 23
• 22
• 21
• 20
• 19
• 18
• 17
• 16
• 15
• 14
• 13
• 12
• 11
• 10
• 9
• 8
• 7
• 6
• 5
• 4
• 3
• 2
• 1

2
1111112732110664177

VOLUME 22
25567
725
719
18254
529
652

[illegible]

20.49E
2E.41
6491
51174.
VCLLME

[illegible][illegible][illegible]

PEAK	OUTFLOW IS	56%, AT TIME	44.25 HOURS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS				564.	417.	139.	67.	13441.	381.
CMS				16.	12.	4.	2.		3.78
INCHES					2.81	3.76	3.78		95.89
MM					71.40	95.47	95.89		278.
AC-FT					207.	276.	278.		343.
THOUS CU M					255.	341.	343.		

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FORMULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS		
				RATIO 1	RATIO 2	RATIO 3
HYDROGRAPH AT	1	1.38	1	0.42	0.50	1.00
	(0.30E 19)		(1011.	1204.	2408.
ROUTED TO	1	1.38	1	28.64)(34.09)(68.18)(
	(0.30E 19)		(338.	564.	1970.
ROUTED TO	1000	1.38	1	9.58)(15.98)(55.79)(
	(0.23E 18)		(338.	564.	1970.
ROUTED TO	1100	1.38	1	9.58)(15.97)(55.79)(
	(0.23E 18)		(338.	564.	1969.
ROUTED TO	1600	1.38	1	9.58)(15.98)(55.76)(
	(0.23E 18)		(338.	564.	1969.
					15.98)(55.76)(

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

RATIO OF PMF	MAXIMUM RESERVOIR W.S. ELEV	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CREST	TCP OF DAM	TIME OF MAX OUTFLOW HOURS	DURATION OVER TCP HOURS	MAXIMUM OUTFLOW CFS	MAXIMUM STORAGE AC-FT	MAXIMUM DEPTH OVER DAM	MAXIMUM RESERVOIR W.S. ELEV	RATIO OF PMF	TIME OF FAILURE HOURS
0.42	659.00	659.00	657.25	657.25	659.00	44.75	0.25	338.	1182.	0.00	659.00	0.42	44.75
0.50	659.19	659.19	874.	874.	1182.	44.25	4.25	564.	1217.	0.19	659.19	0.50	44.25
1.00	659.77	659.77	0.	0.	338.	42.75	7.50	1970.	1330.	0.77	659.77	1.00	42.75

PLAN 1 STATION 10CC

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.42	338.	639.4	44.75
0.50	564.	639.7	44.25
1.00	1970.	640.8	42.75

PLAN 1 STATION 11CC

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.42	338.	650.4	44.75
0.50	564.	651.4	44.25
1.00	1969.	654.2	42.75

PLAN 1 STATION 16CC

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.42	338.	617.5	44.75
0.50	564.	619.2	44.25
1.00	1969.	620.6	42.75

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FLOOD PROTECTION BUREAU

 FLOOD PROTECTION PACKAGE (FPC-1)
 PART 3: HYDROGRAPH, JULY 1978
 LAST MODIFICATION 26 APR 79
 MODIFIED FOR HONEYWELL APR 79

1 AL LAKE CHIRUNKACK DAM
 2 ANALYSIS WITH RATIOS - ANALYSIS
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31

0 15 0 0 0 0 0 0

J 1 3 1

J1 .43 .5 1.0

K 0 1

K1

M 1 C 1.38

P 0 17.5 111 123 132 142

T

V 2.3 1.8

X 2.8 2.8 1

K 1 1

K1 ROUTED HYDROGRAPH AT DAM NO BREACH

Y

Y1 1

Y4657.25 658.2 659

Y5 0 60 338

YA 0 166.4 186.6

YE 641.5 657.25 659.0

YE 657.25

YN 659 3.0 1.5 672

YA 20 C 644.5 .5 657.25 659.1

K 1 1000

K1 LOCATION TDE OF DAM

Y

Y1 1

Y6 .05 .05 .05 639 662 20 .99

Y7 0 662 125 650 240 642 265 639

INFLOW HYDROGRAPH

.716

1

1

1

657.25

1

1

1

1

32	Y7	202	642	450	650	580	660	
33	K	1	1100					
34	K1	LOCATION ROUTE 28						
35	Y				1	1		
36	Y1	1						
37	Y6	.05	.05	.05	638.9	662	100	.001
38	Y7	0	670	60	658	235	648	235 638.9 242 638.9
39	Y7	243	648	345	652	1300	670	
40	K	1	1600					
41	K1	LOCATION SEWAGE PLANT						
42	Y				1	1		
43	Y1	1						
44	Y6	.05	.05	.05	615	700	500	.064
45	Y7	0	700	690	660	1450	620	1450 615 1460 615
46	Y7	1460	620	1950	640	2200	680	
47	K	99						
48	A							
49	A							
50	A							
51	A							
52	A							

1, PLAN 1, RATIC 3

END-OF-PERIOD HYDROGRAPH CRINATES

[illegible][illegible][illegible]

[illegible][illegible]

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

RATIO OF PME	MAXIMUM RESERVOIR W.S. ELEV	ELEVATION STORAGE OUTFLOW	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION EVER TCP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
0.43	659.03	657.25	0.03	1188.	359.	1.75	44.75	43.25
0.50	659.13	657.25	0.13	1207.	365.	1.15	43.75	43.25
1.00	659.29	657.25	0.29	1236.	4084.	1.00	41.50	41.00

PLAN 1 STATION 1000

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.43	359.	639.5	44.75
0.50	365.	641.8	43.75
1.00	4084.	642.3	41.50

PLAN 1 STATION 1100

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.43	359.	650.5	44.75
0.50	3608.	655.9	43.75
1.00	4035.	656.2	41.50

PLAN 1 STATION 1600


RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
0.43	359.	617.7	44.75
0.50	3583.	622.0	44.00
1.00	3954.	622.3	41.50

APPENDIX D
STABILITY COMPUTATIONS

K&E 10 X 10 TO THE INCH • 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

46 0700

LAKE AIRGNACK DAM WALL - EMBANKMENT SECTION




SEGMENT	AREA	DISTANCE FROM TOE
①	312.5 ft ²	10 ft
②	334.4 ft ²	6.9 ft
③	35.0 ft ²	2.75 ft
④	2.5 ft ²	5.5 ft

SCALE 1" = 50'

LAKE AIRBORNE DAM

SPIGWAY SECTION



SEGMENT AREA DISTANCE TO TOE

①	$(2.4)(6.2) = 38.9 \text{ ft}^2$	6.8'
②	$\frac{1}{2}(5.5)(6.2) = 45.4 \text{ ft}^2$	3.7'

SCALE 1" = 50'

INPUT TO STABILITY ANALYSIS PROGRAM

<u>INPUT ENTRY</u>	<u>PROGRAM No.</u>
Unit Weight of Dam (K/ft^3)	0
Area of Segment No. 1 (ft^2)	1
Distance from Center of Gravity of Segment No. 1 to Downstream Toe (ft)	2
Area of Segment No. 2 (ft^2)	3
Distance from Center of Gravity of Segment No. 2 to Downstream Toe (ft)	4
Area of Segment No. 3 (ft^2)	5
Distance from Center of Gravity of Segment No. 3 to Downstream Toe (ft)	6
Base Width of Dam (Total) (ft)	7
Height of Dam (ft)	8
Ice Loading (K/L ft.)	9
Coefficient of Sliding	10
Unit Weight of Soil (K/ft^3)	11
Active Soil Coefficient - K_a	12
Passive Soil Coefficient - K_p	13
Height of Water over Top of Dam or Spillway (ft)	14
Height of Soil for Active Pressure (ft)	15
Height of Soil for Passive Pressure (ft)	16
Height of Water in Tailrace Channel (ft)	17
Weight of Water (K/ft^3)	18
Area of Segment No. 4 (ft^2)	19
Distance from Center of Gravity of Segment No. 4 to Downstream Toe (ft)	20
Height of Ice Load or Active Water (ft)	46

WALL SECTION NORMAL LOADING

11.15	PCL
11.15	PCL
11.2	PCL
10.	PCL
10.	PCL
10.44	PCL
10.44	PCL
6.9	PCL
6.9	PCL
35.	PCL
35.	PCL
11.15	PCL
11.15	PCL
12.	PCL
12.	PCL
11.15	PCL
11.25	PCL
0.	PCL
0.	PCL
0.6	PCL
0.6	PCL
0.06	PCL
0.06	PCL
0.3	PCL
0.3	PCL
3.3	PCL
3.3	PCL
0.	PCL
0.	PCL
16.5	PCL
16.5	PCL
1.5	PCL
13.5	PCL
0.	PCL
0.	PCL
0.0624	PCL
0.0624	PCL
2.5	PCL
2.5	PCL
5.5	PCL
5.5	PCL
16.5	PCL

WALL SECTION ICE LOADING

0.15	RCL
31.2	RCL
31.2	RCL
10.	RCL
10.	RCL
33.44	RCL
33.44	RCL
6.9	RCL
6.9	RCL
35.	RCL
35.	RCL
2.75	RCL
2.75	RCL
12.	RCL
12.	RCL
7.25	RCL
7.25	RCL
10.	RCL
10.	RCL
0.6	RCL
0.6	RCL
0.06	RCL
0.06	RCL
0.3	RCL
0.3	RCL
3.3	RCL
3.3	RCL
0.	RCL
0.	RCL
16.5	RCL
16.5	RCL
13.5	RCL
13.5	RCL
0.	RCL
0.	RCL
0.0624	RCL
0.0624	RCL
2.5	RCL
2.5	RCL
5.5	RCL
5.5	RCL
16.5	RCL

1.5711042

F.S. VS. OVERTURNING

1.641104274

7.3471042

11.271042697

2.1041042

F.S. - SLIDING

1.151042607

WALL SECTION 1/2 PMF

0.15	RCL
11.1	
31.1	RCL
11	
10	RCL
12.1	
13.1	RCL
6.1	
6.1	RCL
35.	
35.	RCL
2.75	
2.75	RCL
12.	
12	RCL
17.25	
17.25	RCL
0.	
0	RCL
0.3	
0.3	RCL
0.06	
0.06	RCL
0.3	
0.3	RCL
3.3	
3.3	RCL
1.43	
1.43	RCL
16.5	
16.5	RCL
No Passive Due To Existing Resisting From Full-Tilt Dam	
0.	
0.	RCL
0.0624	
0.0624	RCL
2.5	
2.5	RCL
5.5	
5.5	RCL
16.1	

No Passive
Due To Existing
Resisting From
Full-Tilt Dam

1.78.52.105. F.S. OVERTURNING

1.78.52.105.

1.424131658- F.S. SLIDING

WALL SECTION PMF

0.15	RCL
11.1	
31.1	RCL
11	
10	RCL
12.1	
13.1	RCL
6.1	
6.1	RCL
35.	
35.	RCL
2.75	
2.75	RCL
12.	
12	RCL
17.25	
17.25	RCL
0.	
0.	RCL
0.6	
0.6	RCL
0.06	
0.06	RCL
0.3	
0.3	RCL
3.3	
3.3	RCL
2.08	
2.08	RCL
No Passive Due To Existing Resisting From Full-Tilt Dam	
0.	
0.	RCL
0.	
0.	RCL
0.0114	
0.0624	RCL
2.5	
2.5	RCL
5.5	
5.5	RCL
16.5	

No Passive
Due To Existing
Resisting From
Full-Tilt Dam

1.78.52.105.

1.78.52.105.

1.40135126.3

SEISMIC ANALYSIS

WALL SECTION

10.	2
10.	RCL
	3
33.44	RCL
33.44	4
6.9	RCL
6.9	5
35.	RCL
35.	6
2.75	RCL
2.75	7
12.	RCL
12.	8
17.25	RCL
17.25	9
0.	RCL
0.	10
0.6	RCL
0.6	11
0.06	RCL
0.06	12
0.3	RCL
0.3	13
3.3	RCL
3.3	14
0.	RCL
0.	15
16.5	RCL
16.5	16
13.5	RCL
13.5	17
0.	RCL
0.	18
0.0624	RCL
0.0624	19
2.5	RCL
2.5	20
5.5	RCL
5.5	46
16.5	RCL
16.5	50
0.05	

1.57128062

7.347454472

2.134443485

SEISMIC ANALYSIS

F.S. OVERTURNING

1.468184354

6.444225537

F.S. SLIDING

1.917688659

SPILLWAY SECTION NORMAL LOADING

0.15 RCL
1
24.2 RCL
38.4 2
6.3 RCL
6.3 3
45.4 RCL
45.4 4
3.7 RCL
3.7 5
0. RCL
0. 6
0. RCL
0. 7
8. RCL
8. 8
16.2 RCL
16.2 9
0. RCL
0. 10
0.65 RCL
0.65 11
0.06 RCL
0.06 12
0.3 RCL
0.3 13
3. RCL
3. 14
0. RCL
0. 15
9. RCL
9. 16
8. RCL
8. 17
2. RCL
2. 18
0.0624 RCL
0.0624 19
0. RCL
0. 20
0. RCL
0. 21
15.23

SPILLWAY SECTION ICE LOADING

0.15 RCL
1
38.4 RCL
38.4 2
6.3 RCL
6.3 3
45.4 RCL
45.4 4
3.7 RCL
3.7 5
0. RCL
0. 6
0. RCL
0. 7
8. RCL
8. 8
16.2 RCL
16.2 9
10. RCL
10. 10
0.65 RCL
0.65 11
0.06 RCL
0.06 12
0.3 RCL
0.3 13
0. RCL
0. 14
0. RCL
0. 15
9. RCL
9. 16
8. RCL
8. 17
2. RCL
2. 18
0.0624 RCL
0.0624 19
1. RCL
1. 20
0. RCL
0. 21
15.23

1.24

1.98

1.390507400

F.S. OVERVERTURNING

F.S. SLIDING

.37

-16.84000000

.621003408

$\frac{1}{2}$ PMF

1. $\frac{1}{2}$

AME

25 48

F.S. OVERTURNING

11-552

F.S. SLIDING

. 94059; 7262

100-62-26794

1.05270023

SPILLWAY SECTION SEISMIC ANALYSIS

38.9	RCL
38.9	2
6.8	RCL
6.3	3
45.4	RCL
45.4	4
3.7	RCL
3.7	5
0.	RCL
0.	6
0.	RCL
0.	7
8.	RCL
8.	8
16.2	RCL
16.2	9
0.	RCL
0.	10
0.65	RCL
0.65	11
0.05	RCL
0.05	12
0.3	RCL
0.3	13
3.	RCL
3.	14
0.	RCL
0.	15
9.	RCL
9.	16
8.	RCL
8.	17
2.	RCL
2.	18
0.0634	RCL
0.0624	19
0.	RCL
0.	20
0.	RCL
0.	46
15.25	RCL
15.25	50
0.05	

1.24978196

1.981223804

1.396537486

1.147997322

1.277967182

1.222111111

SEISMIC ANALYSIS

F.S. OVERTURNING
 F.S. SLIDING

APPENDIX E

REFERENCES

APPENDIX E


REFERENCES

- 1) U.S. Department of Commerce; Weather Bureau;
Hydrometeorological Report No. 33 - Seasonal Variation of the Probable
Maximum Precipitation East of the 105th Meridian for Areas from 10 to
1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours, April 1956.
- 2) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition,
McGraw-Hill, 1963.
- 3) University of the State of New York, Geology of New York, Education
Leaflet 20, Reprinted 1973.
- 4) Elwyn E. Seelye, Design, 3rd edition, John Wiley and Sons, Inc., 1960.
- 5) U.S. Department of the Interior, Bureau of Reclamations;
Design of Small Dams, 2nd edition (rev. reprint), 1977.

APPENDIX F


DRAWINGS

DAM SITE



VICINITY MAP

LAKE ADIRONDACK DAM
I.D. No. N.Y. 621



TOPOGRAPHIC MAP

LAKE ADIRONDACK DAM
I.D. NO. NY 621

NEW YORK STATE DEPARTMENT OF
PUBLIC WORKS

DIVISION OF HIGHWAYS

DATE: 12-1-21
128-928


PROJECT: *Gravel Road*


BY: *J. H. Smith*


APPROVED:


CHIEF ENGINEER


DATE: 12-1-21














REPAIRS
FOR
TOWN OF INDIAN
HAMILTON
MAY-1931 NEW YORK



Note: Present stone dam built in 1910 and in excellent condition.
Elevation top new structure is 1659 ft.



REPAIRS TO DAM
FOR
TOWN OF INDIAN LAKE
HAMILTON CO.
MAY 1931 NEW YORK. C.S. Carroll.




built in 10 and in excellent condition.
structure is 1659 ft.

Sheet #2

5

6




upstream face to be waterproofed
with asphalt

letty
for

stream face to be waterproofed

Ledge reinforced
for foundation



Gravelly sand

Gravelly sand

Gravelly sand

Left side 2'0" 3'0"
Right side 1'0" 1'0"

2'0" 6'0"
2'0" 2'0"
2'0" 1'0"

2

E/1651

1659

1200
Vert. 11. 10.0 m

26.00
10.00

16

Removal

CRANE


Grav.

12.00

Crane

Water 5.00 2.00

1.00 2.00 2.00
1.00 2.00 2.00



let 190
for 1


Ledge reinforced
for foundation



E1651

Gravel
Gravel

Section 28



Gravel fill

Gravel

Water

Port 20' 3' 0' 0'
12' 3' 0' 0'

12' 3' 0' 0'
12' 3' 0' 0'

12' 3' 0' 0'

5

